

High Wall Heat Pump Ductless System

Indoor Model: **40MHHQ12---3**

Submittal Data

Job Data: Location:

Buyer: Buyer P.O. #: Carrier #:

Unit Number: Model Number:

Performance Data Certified By: Date:



STANDARD FEATURES

- Up-Down Louver control (fixed or swing)
- Remove filter from the top
- Improved serviceability with easy access to fan and electrical connections
- Four fan speeds
- Sleep Mode
- Follow Me (senses temperature at handheld remote)
- Quiet operation
- Aluminum Blue Hydrophilic pre-coated fins

Controls:

- Wireless Remote Controller included with indoor unit
- Optional Wired Remote Controller KSACN0401AAA

LIMITED WARRANTY*

- 10 year limited to original purchaser on compressor and parts upon timely registration, otherwise 5 years

*For residential applications. See warranty for full details.

System	Size	12	
	Indoor Model	40MHHQ12---3	
Electrical	Voltage, Phase, Cycle	V/Ph/Hz	208/230-1-60
	Power Supply	Powered from outdoor unit	
	MCA - Rated Current	A.	0.1
Controls	Wireless Remote Controller (°F/°C Convertible)	Standard	
	Wired Remote Controller (°F/°C Convertible)	Optional	
Operating Range	Cooling Indoor DB Min -Max	° F (° C)	62~90 (17~32)
	Heating Indoor DB Min -Max	° F (° C)	32~86 (0~30)
Piping	Pipe Connection Size - Liquid	in (mm)	1/4 (6.35)
	Pipe Connection Size - Suction	in (mm)	1/2 (12.7)

Indoor Coil	Face Area (sq. ft.)	Sq. Ft.	1.76
	No. Rows	2	
	Fins per inch	21	
	Circuits	2	
Indoor	Unit Width	in (mm)	32.00 (813)
	Unit Height	in (mm)	11.81 (300)
	Unit Depth	in (mm)	7.75 (197)
	Net Weight	lbs (kg)	18.74 (8.5)
	Number of Fan Speeds	4	
	Airflow (lowest to highest)	CFM	212/282/324/353
	Sound Pressure (lowest to highest)	dB(A)	31/36/42/43
	Air throw Data	ft (m)	22.6 (6.9)
	Moisture removal	Pint/h (L/h)	3.43 (1.62)
	Field Drain Pipe Size O.D.	in (mm)	0.625 (16)

Performance may vary based on the outdoor unit matched to. See compatible outdoor units pages for Performance Data.

Accessories

53DS-900---118	Condensate Pump (208/230V)
KSACN0401AAA	Wired Remote Control 7 Day Programmable
53DS-900---008	Insulated 25' Line Set - 1/4" x 1/2"

Construction View

